FILL CHART

Material Location	Description	Mat	erial C	lassification	Compaction/Density Requirement (NOTE 3)
FINAL FILL Fill starting from the top of the embedment fill layer. (NOTE 1 and 2)	Suitable Fill Materials as noted in the Project Geotechnical Report and noted on the Site Design Engineer's Plans	See Project Geotechnical Report and Site Design Engineer's Plans		·	Plate Compact or Static Roll loose lifts to densify fill. Use at least two full passes of the equipment to level the layer. Continue until 24 inches of total fill thickness has been placed above the tank. For AASHTO M145 soils, a minimum of 95% of the Standard Proctor Maximum Dry Density is recommended. After 24 inches of fill is placed, place fill in accordance with the engineer of record's relative compaction requirement or to 95% of the Standard Proctor Maximum Dry Density - whichever is greater.
EMBEDMENT FILL Fill Immediately Surrounding the sides and top of tank (NOTE 4) BEDDING FILL Fill Immediately below the tank (NOTE 4)	Sand-Gravel Mixtures or Open-Graded Crushed Aggregate Blends	AASHTO M145 A-1, A-2-4, A-3	or		Plate Compact or Static Roll loose lifts to densify fill. Use at least two full passes of the equipment to level the layer. For AASHTO M145 soils, a minimum of 95% of the Standard Proctor Maximum Dry Density is recommended.

NOTE 1: This layer can include pavement subbase

Cover Depth as Specified

By Site Design Engineer

(See Cover Chart)

6" Minimum

NOTE 2: If open-graded aggregates are used for embedment fill, fines migration from the final to embedment fill layer may be reduced by installing a layer of 6 oz non-woven geotextile fabric at the final and embedment fill interface.

300HD Side Panel (Part #138461)

-FINAL FILL (See Fill Chart)

-EMBEDMENT FILL (See Fill Chart)

TYP. for all exterior sides

-300HD Half-Module

(Part # 138462) TYP.

NOTE 3: See Construction Equipment Table for more information for construction equipment limitations.

See

NOTE 4: Import or native soils may be used if the soils meet the material classification listed. Fill material should be selected based on classification, groundwater conditions, and tank invert elevation

-Surface Material (Pavement Section or

Topsoil) as Specified by Site Design Engineer

-6 oz Non-Woven Geotextile (outer)

1 LAYER 300HD

INFILTRATION CROSS SECTION

NOTE 1: The minimum width of sidewall backfill is 12" or large enough to accommodate

around entire tank by Others

selected compaction equipment, whichever is greater.

CONSTRUCTION EQUIPMENT CHART

Equipment Make (NOTE 1)	Maximum Gross Vehicle Weight (lbs)	Minimum Fill Depth over Tank (in)
Plate Compactor	1,500	6
Compact Track Loader (NOTE 2)	7,500	6
Rubber-Tired Skid Steer (NOTE 3)	7,500	14
Low Ground Pressure Tracked Vehicles (NOTE 4)	20,000	14
Roller - Static Mode	12,000	18
Roller - Vibratory Mode	12,000	24
Dump Trucks and Pans	NOT	E.5

NOTE 1: Vehicles shall make straight runs only across tank footprint.

NOTE 2: Maximum ground pressure = 5 psi NOTE 3: Maximum axle load = 5,250 lbs

NOTE 4: Maximum ground pressure = 7 psi

NOTE 5: Contact ACO for more information regarding dump truck and pan traffic during construction.

NOTE 6: Backfill material may be temporarily unloaded near the excavation. Material shall not be stockpiled near the excavation for

Remote Access Cover Vented (Part #314133) or Solid (Part #314132) - See NOTE 1

-Extension Shaft (Part #314038) Concrete Load Distribution Plate

by Others - See NOTE 2

Remote Access Plate

(Part #314075) - See NOTE 3

300HD Side Panel (Part #138461) TYP. for all

exterior sides


longer than 24 hours.

Steel Bands by Others



PIPE WRAP

NTS



-Cut Geotextile and wrap around

-6 oz Non-Woven Geotextile (outer)

SIDE PANEL PIPE **DIAMETER CHART**

COVER CHART

Live Loading Condition Non-Trafficked Areas (i.e.

Landscaping) Passenger Vehicles Parking Lot (i.e. Gross Vehicle Weight <10,000 lbs) Passenger Vehicle Parking Lot with one weekly AASHTO HS-20

vehicle

Frequent AASHTO HS-20 Traffic

Passenger Vehicle Parking Lot

with one weekly AASHTO HS-25

Frequent AASHTO HS-25 Traffic

below the invert of the tank

NOTE 1: Minimum Cover Thickness in non-trafficked areas is based on landscape surface with a 40 degree load distribution. In trafficked areas, Minimum Cover Thicknesses are based on an

asphalt-surfaced pavement with a 30 degree load distribution. NOTE 2: Calculations assume backfill with a minimum 32-degree

angle of internal friction and a maximum density of 120 lbs per

cubic foot, and a seasonal groundwater elevation at least 2 feet

Cover Thickness (inches)

134

134


134

134

134

Inlet/Outlet Pipe Diameter				
Minimum	Maximum			
4 inches	6 inches			

NOTE 1: Cut inlet / outlet pipe hole prior to NOTE 2: Contact ACO for guidance for inlet / outlet pipes larger than 6-inch



Cut hole based on pipe diameter and slip-fit install pipe. See Pipe Diameter

6 oz Non-Woven Geotextile (outer) around entire tank by Others

1 LAYER 300HD

PIPE INSTALLATION

-BEDDING FILL (See Fill Chart) -Engineer of Record responsible for checking that subgrade soils meet the bearing and settlement requirements during design and construction

1 LAYER 300HD **ACCESS POINT CROSS SECTION**

> NOTE 1: Ventilation may be crucial to reducing the pressure build up within the system. If solid access covers are used, alternative methods of ventilation are recommended. NOTE 2: Concrete Load Plate not required for unpaved applications. Consult Engineer of Record for requirements NOTE 3: The Remote Access Plate is approximately the size of half of a half-module. The half-module at the top of the tank must be cut in half to accommodate the Remote Access Plate

-300HD Half-Module (Part # 138462)

TYP, under access point

CHECKED BY J Jonke A Frye DATE REV. 12/11/2024

STORMBRIXX STANDARD DETAILS **300HD SYSTEM - 1 LAYER - INFILTRATION**

ACO, INC.

WEST SALES OFFICE

CASA GRANDE, AZ 85122 Tel. (888) 490-9552 Fax (520) 421-9899

EAST SALES OFFICE 9470 PINECONE DRIVE

MENTOR, OH 44060 Tel. (800) 543-4764 Fax (440) 639-7235

www.acoswm.com

SOUTHEAST SALES OFFICE 481 MUNN RD. SUITE #225 FORT MILL, SC 29715

Tel. (440)-639-7230 Fax (803)-802-1063

DRAWN BY